

SHARKEY
C 45
2-17-69

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201
WATER WELL DRILLERS LOG

CODED

2-17 1969 DAVID BERRY SHARKEY
date well completed firm name county well located

LANDOWNER:	description of formations encountered	from	to
HARRY CARPENTER	clay	0	34
Rolling Fork, Miss. (mailing address)	sand	34	95
	gravel	95	140
WELL LOCATION:	clay	140	218
sec. 36 T. 13 N. R. 2 E. W. 5	sand	218	309
1 1/2 miles NW of Rolling Fork	sand with shale	309	340
(distance) (direction) (nearest town)	sand	340	492
	sand with shale	492	680
WELL PURPOSE: FARM	rock	680	681
(home, irrigation, municipal, industrial)	shale with rock	681	706
WELL COMPLETION DATA:	shale with sand	706	767
(1) diameter (inches) 4x3x2 1/2	sand	767	798
(2) total depth (feet) 1206	sand with shale	798	859
(3) static water level (feet) 21 below top of ground.	hard shale	859	889
(4) casing STD. BLACK (material), 1150 (depth)	shale with rock	889	920
4x3x2 1/2 if telescope see back. (size)	shale	920	950
(5) screen 40' (length), 1150 (depth to top)	shale with sand	950	981
2 1/2" STAINLESS (size) (material)	sand with shale	981	1010
(6) pump 5 SUB (HP) (yield gpm)	shale	1010	1089
Ele. (type power)	sand	1089	1149
(7) electric log yes (yes or no)	shale	1149	1180
Mid. Sec. Agency (organization running log)	sand	1180	1241
(8) how well bottom plugged 1 1/2" plug			
DRILLERS REMARKS:			

MAR 21 1969

MISS. BD. OF WATER COMM.

If well telescopes please sketch and show depths.


GROUND LEVEL

200'
of
4"

350'
of
3"

600'
of
2 1/2"

20'
of
SCX 2211
8" ID
PIPE
20'
of
SCX 2211
8" ID
TAIL PIPE



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.