

SHARKEY  
 J31  
 9-26-77  
 Elong #94  
 9-20-77  
 date well completed

MISSISSIPPI  
 BOARD OF WATER COMMISSIONERS  
 416 North State Street  
 Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

*Jefcoat Drilling Co.* *Sharkey*  
 firm name county well located

LANDOWNER:  
*L.W. Cattlege*  
*Onward miss.*  
 (mailing address)

description of formations encountered	from	to
<i>Clay &amp; top soil</i>	0	40
<i>Sand</i>	40	65
<i>Gravel</i>	65	135
<i>Shale</i>	135	340
<i>Sand</i>	340	705
<i>Shale</i>	705	1005
<i>Sand</i>	1005	1048
<i>Shale</i>	1048	1113
<i>Sand</i>	1113	1287
<i>Shale</i>	1287	1420
		70

WELL LOCATION:  
 sec. 17 T. 10 N R. 7 W E  
*2/10* miles *south* of *Onward*  
 (distance) (direction) (nearest town)

WELL PURPOSE: *Farm*  
 (home, irrigation, municipal, industrial)

- WELL COMPLETION DATA:
- (1) diameter (inches) 4x2
  - (2) total depth (feet) 1252
  - (3) static water level (feet) 20 below top of ground.
  - (4) casing stal 1217  
 (material) (depth)  
4x2 if telescope see back.  
 (size)
  - (5) screen 30ft 1217  
 (length) (depth to top)  
2" Stal  
 (size) (material)
  - (6) pump 2 43  
 (HP) (yield gpm)  
pc  
 (type power)
  - (7) electric log no  
 (yes or no)  
MHS  
 (organization running log)
  - (8) how well bottom plugged stal pin

CODED

RECEIVED  
 DEC 16 1977

DRILLERS REMARKS:

MISS. BD. OF WATER COMM

If well telescopes please sketch and show depths.

GROUND LEVEL


150 ft  
4"

2" pipe 1067 ft

TD 1252

2x 1/2" screen 30 ft screen  
5 ft tail pipe

If more than one screen, show locations of each on sketch.



SECTION \_\_\_\_\_

Please indicate well location X.

ADDITIONAL INFORMATION

Multiple horizontal lines for additional information.