

SIMPSON
M7
6-24-63

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

not in phone book

Date: June 24, 1963, Driller: Ben Burney

(Name)

CODED

- (1) Owner of Land: C. H. Shows
(Name)
1112 Glenn Erin, Jackson
(Address) 12 921
- (2) Location: 1/4, 1/4, Sec. T. R.,
7 miles North West of New Hebron
(distance) (direction) (Nearest Town)
- (3) Topography: Hilly
(Hilly) (Flat) (Level)
- (4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Information upon completion of well:

- (1) Diameter 4 inches.
- (2) Total Depth 294' feet.
- (3) Water Level 218 feet below top of ground.
- (4) Cased to 276', Size 2"
- (5) Screen: Size 2 1/2", Length 5'
- (6) Were any formations sealed against pollution?
X yes, no.


If YES depth of formation From Surface

Why To prevent surface pollution

Drillers Remarks:

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Top Soil	6	6
Sand & Gravel	18	24
Pipe Clay	41	65
Sand	11	76
White & Red Pipe Clay	14	90
Grey Clay	25	115
Rock & hard	6	121
Layers of Sand & Rock	2	123
Hard Rock	3	126
Tight Blue Clay	39	165
Soft Grey Formation	9	174
Tight Shale	32	206
Shell & Shale (Soft)	26	232
Fine Sand in Layers	12	244
Fine Quick Sand	15	259
All Sand Best at 270' to 285'	33	292
Shale	2	294

CODED



(Use Back Side)

Well No.

