

SMITH  
A 41  
5/24/79

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

5-24 79 Griner Drilling Smith  
date well completed firm name county well located

LANDOWNER:  
American Quasar Petroleum  
1326 Capital Towers  
Jackson, MS 39120  
(mailing address)

description of formations encountered	from	to
Clay	0	189
clay + little shell	190	300
clay + rock	300	316
clay + shell	316	357
sand	357	373
clay + shel	373	395
fine sand	395	445
clay + sand	445	495
sand	495	546
clay + sand	546	599
fine sand	599	630
sand + clay	630	650
clay	650	672

WELL LOCATION: 600' N + 1953' E  
sec. 1 T. 4 N R. 6 E of  
Smith Co. Polkville  
(distance) (direction) (nearest town)

WELL PURPOSE: oil field supply  
(home, irrigation, municipal, industrial)

- WELL COMPLETION DATA:
- (1) diameter (inches) 3"
  - (2) total depth (feet) 672'
  - (3) static water level (feet) 110' below top of ground.
  - (4) casing steel, 546' (material) (depth)  
3" (size) if telescope see back.
  - (5) screen 42', 504' (length) (depth to top)  
3', perforated (size) (material)
  - (6) pump - 75 (HP) (yield gpm)  
AC (type power)
  - (7) electric log - (yes or no)  
(organization running log)
  - (8) how well bottom plugged - orange peel

Miss. Board of Water Comm.


MAY 29 1979

RECEIVED

DRILLERS REMARKS:

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION \_\_\_\_\_

Please indicate well location X.

ADDITIONAL INFORMATION

A series of horizontal lines for recording additional information, starting below the 'ADDITIONAL INFORMATION' header and extending to the bottom of the page.

If more than one screen, show locations of each on sketch.