

SMITH
B4
2-10-61

WATER WELL DRILLERS LOG

Date: 2/10, 1961, Driller: James McGee County Smith
(Name)

(1) Owner of Land: Braxton L. Hawkins
Take Hwy. 35 South from Forest and
to Burns road and this place is about
3 miles on the right (distance)
(2) Location: 1/4, 1/4, Sec. 36 T 4N R 7E
 miles of
(distance) (direction) (Nearest Town)
(3) Topography: X
(Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic.
(Domestic Irrigation
Municipal, Industrial, Other)

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|---|------------------------|---------------|
| Brown clay. | 0- | 18 |
| Rock. | 18- | 20 |
| Clay. | 20- | 37 |
| Rock & mucky sand. | 37- | 42 |
| Clay & stks. sand. | 42- | 65 |
| Clay. | 65- | 142 |
| Clay & stks. sand. | 142- | 152 |
| Clay. | 152- | 312 |
| Shale. | 312- | 425 |
| Rock. | 425- | 431 |
| Shale & stks. rock. | 431- | 481 |
| Shale. | 481- | 511 |
| Sandy shell. | 511- | 521 |
| Clay & stks. sand. | 521- | 531 |
| Clay. | 531- | 581 |
| Clay & stks. shale. | 581- | 591 |
| Mucky clay & stks. sand. | 591- | 621 |
| Fine sand. (Screen set) | 621- | 641 |


Information upon completion of well:

- (1) Diameter 2 inches.
(2) Total Depth 641 feet.
(3) Water Level 165 feet below top of ground.
(4) Cased to 621', Size 2"
(5) Screen: Size 2", Length 20'
(6) Were any formations sealed against pollution?
 yes, X no.

If YES depth of formation

Why

Drillers Remarks: Fair well.



(Use Back Side)

Well No.

