

C7

5-28-63

WATER WELL DRILLERS LOG

Date: 5/28, 1963, Driller: Frank Dwyer County Jeff  
 (Name)


(1) Owner of Land: T. A. Key  
 (Name)  
Homewood Miss.  
 (Address)  
 (2) Location: 1/4, 1/4, Sec. 8 T. R.  
2 1/2 miles South of Homewood  
 (distance) (direction) (Nearest Town)  
 (3) Topography:  (Hilly)  (Flat)  (Level)  
 (4) Purpose of Well: \_\_\_\_\_  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials. Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red clay	0	12
Sand + Clay		60
Clay + Sand		92
Blue clay		157
Rock		160
Clay		312
Shale		362
Shale + Shls Rock		412
Shale		433
Shale + Shls Rock		443
Shale		478
Fine Sand		483
Fine sand + Shls Clay		503
Shale		520
Fine Sand + Clay		553
Shale		593
Fine Sand + Shls Clay		613
Fine sand		632

Information upon completion of well:

(1) Diameter 2" inches.  
 (2) Total Depth 632 feet.  
 (3) Water Level 180 feet below top of ground.  
 (4) Cased to 617, Size 2"  
 (5) Screen: Size 2", Length 15ft.  
 (6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes,  no.

If YES depth of formation \_\_\_\_\_  
 Why \_\_\_\_\_  
 Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

