

Sunflower  
 F21  
 6-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

6/16/66  
 2215

WATER WELL DRILLERS **CODED**

Date: June 7, 1966, Driller: Layne-Central Company County Sunflower  
 (When well drilled) (Name) (Where well is located)

(1) Owner of Land: Kelly R. Mahan  
 Brooks Farm -  
 (Name)  
 Drew, Mississippi  
 (Address)

(2) Location: 1/4, 1/4, Sec ~~2~~ 22 R 3,  
 1/4 miles east of Drew  
 (distance) (direction) (Nearest Town)

(3) Topography: flat  
 (Hilly) (Flat) (Level)

(4) Purpose of Well: irrigation  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Sandy clay	18	18
Fine sand	4	22
Little coarse sand	30	52
Coarse sand	20	72
Gravel & sand	13	85
Coarse sand, few pea gravel	17	102
Coarse sand, gravel & rock	27	129
Coarse sand & gravel	3	132

Information upon completion of well:

(1) Diameter 16 inches.

(2) Total Depth 132 feet.

(3) Water Level 20' 4" feet below top of ground.

(4) Cased to 73' 9", Size 16"

(5) Screen: Size 16", Length 60'

(6) Were any formations sealed against pollution?  
 yes, no no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_


Drillers Remarks: \_\_\_\_\_

Yield in gpm: \_\_\_\_\_

Size pump: \_\_\_\_\_

Type power: \_\_\_\_\_

**CODED**



Mail this copy to Board of Water Commissioners 429 Miss. St. Jackson, Miss.

