

SUNF.  
L 37  
3-12-65

U595-2008

WATER WELL DRILLERS LOG

Date: MAR. 12, 1965, Driller: DELTA DRILLING Co. County: SUNFLOWER

(Name)

(1) Owner of Land: GRADY BENNETT ETAL.  
(Name)

BLAINE, MISS.  
(Address)

(2) Location: NE 1/4, NE 1/4, Sec. 17 T20R3W

           miles            of             
(distance) (direction) (Nearest Town)

(3) Topography:             
(Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC  
(Domestic Irrigation  
Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter 4 inches.

(2) Total Depth 1414 feet.

(3) Water Level            feet below top of ground.

(4) Cased to 1414, Size 4" 105'  
3" 668'  
2" 631'

(5) Screen: Size 2", Length 20

(6) Were any formations sealed against pollution?  
           yes,            no.


If YES depth of formation           

Why           

Drillers Remarks: WELL SET 1414'  
WITH 1/2 H.P. RED JACKET SUB-  
MERSIBLE PUMP SET IN WELL

30'-LAP OF 2" IN 3" PIPE

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
GUMBO	54	54
SAND	33	87
GRAVEL	73	160
GUMBO	95	255
SAND	227	482
GUMBO	103	585
SAND	40	625
GUMBO	142	767
SHALE	41	808
GREEN SAND	61	869
GUMBO	40	909
SHALE	23	932
SAND W/ROCK	60	992
SHALE	42	1034
GUMBO	20	1054
SHALE	204	1258
GUMBO	57	1315
SAND	106	1421
GUMBO	67	1488
SHALE	48	1536
GUMBO	65	1601



(Use Back Side)

Well No.

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...