


TALLA.
D9
10-30-62

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG CODED

Date: OCT 30, 1962, Driller: DELTA DRILLING Co. County TALLAHATCHIE
(Name)

	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
(1) Owner of Land: <u>MRS CARLAND MELTON</u> (Name)	GUMBO	10	10
<u>BRAZIL, MISS.</u> (Address)	SAND	72	82
(2) Location: <u>SW 1/4, NE 1/4, Sec. 5 T28N R14W</u>	GRAVEL	50	132
_____ miles _____ of _____ (distance) (direction) (Nearest Town)	GUMBO	98	230
(3) Topography: _____ (Hilly) (Flat) (Level)	SAND	49	279
(4) Purpose of Well: <u>DOMESTIC</u> (Domestic Irrigation Municipal, Industrial, Other)	SHALE	76	355
Information upon completion of well:	GUMBO	12	367
(1) Diameter <u>3</u> inches.	SHALE IMPURE	68	435
(2) Total Depth <u>1009</u> feet.	SAND COBBLES	44	479
(3) Water Level <u>FLOWS</u> feet below top of ground.	GUMBO	64	543
(4) Cased to <u>801'</u> , Size <u>3" 501'</u> <u>2" 300'</u>	SAND	86	629
(5) Screen: Size <u>2</u> , Length <u>20'</u>	SHALE	41	670
(6) Were any formations sealed against pollution? _____ yes, _____ no.	SAND	43	713
If YES depth of formation _____	GUMBO	20	733
Why _____	SAND	68	801
Drillers Remarks: <u>21' LAP OF 2" IN</u>	SHALE	28	829
<u>3" PIPE.</u>	GUMBO	28	857
	SHALE	36	893
	GUMBO	34	927
	SHALE	42	969
	GUMBO	40	1009



(Use Back Side)

Well No.

