

4/15/65

H-22

8-21-56

WATER WELL DRILLERS LOG

251

Date: August 21, 1956, Driller: Layne-Central Company, County Tallahatchie

CODED

(Name)

CODED

- (1) Owner of Land: Jack Webb
(Name)
Sumner, Mississippi
(Address) 21, 28, 29
- (2) Location: 1/4, 1/4, Sec. 13 T29R2W
8 miles southeast of Rome
(distance) (direction) (Nearest Town)
- (3) Topography: flat
(Hilly) (Flat) (Level)
- (4) Purpose of Well: irrigation
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Top soil	5	5
Clay	39	44
Coarse sand	8	52
Coarse sand	10	62
Sand & pea gravel	10	72
Sand & gravel	14	86
Sand & pea gravel	6	92
Coarse sand & gravel	22	114

Information upon completion of well:


- (1) Diameter 16x12 inches.
- (2) Total Depth 114 feet.
- (3) Water Level 18' - 11" feet below top of ground.
- (4) Cased to 62' 2' swage Size 16"
- (5) Screen: Size 12", Length 50'
- (6) Were any formations sealed against pollution?
no yes, no no.

CODED

If YES depth of formation _____

Why _____

Drillers Remarks: _____
1940 GPM
engine drive



(Use Back Side)

Well No.

1900

1901

1902

1903

1904

1905

1906

1907

1908