

Tishomingo  
L 19  
3-69

MISSISSIPPI  
 BOARD OF WATER COMMISSIONERS  
 416 North State Street  
 Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

MARCH 1969 J.W. Webb & Sons Tishomingo  
 date well completed firm name county well located

LANDOWNER:

DENNIS WATER ASDN,  
Belmont, Miss.  
 (mailing address)

description of formations encountered

from to

<u>Red SAND</u>	<u>0</u>	<u>40</u>
<u>Red CLAY</u>	<u>40</u>	<u>75</u>
<u>GRAVEL</u>	<u>75</u>	<u>135</u>
<u>Red CLAY</u>	<u>135</u>	<u>140</u>

WELL LOCATION:

sec. 15 T 6 N R 10 E  
2 miles N of Belmont  
 (distance) (direction) (nearest town)

WELL PURPOSE: COMMUNITY  
 (home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- diameter (inches) 10"
- total depth (feet) 140'
- static water level (feet) 52 below above top of ground.
- casing Steel, 81'  
 (material) (depth)  
10" if telescope see back.  
 (size)
- screen 50, 85'  
 (length) (depth to top)  
6", SS  
 (size) (material)
- pump 7 1/2 75  
 (HP) (yield gpm)  
ELOC  
 (type power)
- electric log NO  
 (yes or no)  
 (organization running log)
- how well bottom plugged

CODED

APR 10 1969

DRILLERS REMARKS:

MISS. BD. OF  
 WATER COM.

⑦

If well telescopes please sketch and show depths.

GROUND LEVEL

10" casing


75' BEGIN 6" PIPE

81'

BEGIN SCREEN

137'

BOTTOM



SECTION 15

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.