

WALTHAM
J 33
4-20-72

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

CODED

4, 20, 1972 - Red Martin Water Well Drilling Co.
date well completed firm name county well located

LANDOWNER:

Mr + Mrs Bekley E
Craw #7 Iylertown
(mailing address) miss

description of formations encountered

from to

WELL LOCATION:

sec. 26 T. 1 N. R. 11 E.
10 miles S.E. of Iylertown
(distance) (direction) (nearest town)

WELL PURPOSE:

(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 4"
- (2) total depth (feet) 195'
- (3) static water level (feet) 90' below top of ground.
- (4) casing PVC, 185' (material) (depth)
4" (size) If telescope see back.
- (5) screen 10', 185' (length) (depth to top)
1012 PVC (size) (material)
- (6) pump 1/2 hp, 8 (HP) (yield gpm)
220 AC. (type power)
- (7) electric log No (yes or no)

(organization running log)

(8) how well bottom plugged

Sand Shut Back wash Valve

DRILLERS REMARKS:


Top Clay 0 20'
Dry Sand 20 80
Pec. Gravel 80 84
Red Chalk 84 105
fine sand 105 135
Blue sand 135 170
fine sand 170 180
Coarse sand 180 195

MAY 15 1972

MISS. BD. OF
WATER COMMISSIONERS

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,
show locations of each on sketch.