

WARREN
F

WATER WELL DRILLERS LOG

7306

Date: 8/29, 1961, Driller: D H Williams County Warren
8-29-61 (Name)

(1) Owner of Land: Rickard Sutton
R Route (Name)
4 1/2 miles North Hy 61 Vicksburg
Barfield Lot 7+8 (Address)
(2) Location: 1/4, 1/4, Sec. T. R.
West Side R.R.
4 miles north of Vicksburg (distance) (direction) (Nearest Town)
(3) Topography: Flat (Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic (Domestic Irrigation Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick-ness Feet	Depth Feet
Locator West Side Hy 61		
also West of Hwy 61		
1 to 15 ft Surface Rock Clay		
15 to 25 Grey Clay		
25 - 35 " + Shells		
35 to 75 Blue Gumbo (Shale)		
75 95 Sandy Blue Gumbo		
95 to 125 Gumbo = Sticky		
Comes up around Drill in Sheets		
125 - 135 More Like Sand Hard		
135 145 Grey Sand - Forest Hill		
145 - 155 all Sand except 1' shale		
155 to 183 all Grey Sand Fine		
183 - 185 2 ft Gumbo		
Set 20 ft 90 GA Strainer		
2 - 1" Wash Out Valves on Bottom		
Gravel Packed 40 ft		
1/2 Hy Fairbanks Valve 18" Prop		
Cylinder Set at 126 ft		
42 gal Tank		

Information upon completion of well:

(1) Diameter 2" inches.
(2) Total Depth 185 feet.
(3) Water Level 20 feet below top of ground.
(4) Cased to 160', Size 2" Pipe.
(5) Screen: Size 9" 90 GA, Length 20 ft.
(6) Were any formations sealed against pollution?
yes, no.

If YES depth of formation Top-down 8 feet
Why Keep out Surface Water

Drillers Remarks:
Gravel Packed around Screen
up 40 feet Per Gravel



Well No.

