

WARREN

KZ

4-11-62

WATER WELL DRILLERS LOG

CODED

Date: 4/2 to 4/11, 1962, Driller: Johnnie Beasley, County Warren

(Name)

(1) Owner of Land: Troy L. Goss  
(Name)

Rt. 3, Box 127, V. burg, Miss.  
(Address)

This well located East of Culkin  
(2) Location: 1/4, 1/4, Sec. 2 T16R4,  
about 4 miles.  
12  
\_\_\_\_\_ miles \_\_\_\_\_ of \_\_\_\_\_  
(distance) (direction) (Nearest Town)

(3) Topography: x  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Brown silt.	40	40
Red sand.	60	100
Sand & gravel.	65	165
Brown silt.	21	186
Blue clay & stks. gravel.	19	205
Sand.	4	209
Lime rock.	119	328
Shale & lime stone.	66	394
Hard shale & stks. rock.	510	904
Soft shale & lime.	17	921
Shale, shell, mucky sand.	21	942
Shale & lignite.	21	963
Hard shale.	15	978
Soft shale.	52	1030
Silt sand & stks. shale.	38	1068
Fine sand.	4	1072
Sand & Stks. shale.	21	1093
Fine sand.	21	1114
Sand. (Screen setting.)	21	1135

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 1135 feet.

(3) Water Level 220 feet below top of ground.

(4) Cased to 1120', Size 2"


(5) Screen: Size 2", Length 15'

(6) Were any formations sealed against pollution?  
\_\_\_\_\_ yes, x no.

If YES depth of formation \_\_\_\_\_  
Why \_\_\_\_\_

Drillers Remarks: Good well.

CODED



(Use Back Side)

Well No.

Retain this copy for your office files.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100