

K 3001
9-6-60

WATER WELL DRILLERS LOG

K 301

Date: 9/6, 1960, Driller: D.H. Williams County Warren
(Name)

H E + J B Johnson

(1) Owner of Land: _____
(Name)
Route 5, Box 159 B Vicksburg Miss
(Address)

(2) Location: _____ 1/4, _____ 1/4, Sec: *37* T *16N* R *4E*
3 miles *SW* of *Bovina*
(distance) (direction) (Nearest Town)

(3) Topography: _____
(Hilly) (Flat) (Level)

(4) Purpose of Well: *House + Stock*
(Domestic Irrigation
Municipal, Industrial, Other)

Information upon completion of well:

(1) Diameter *2* inches.

(2) Total Depth *189* feet.

(3) Water Level *60* feet below top of ground.

(4) Cased to *177*, Size *2"*

(5) Screen: Size *2"*, Length *12ft*.


(6) Were any formations sealed against pollution?
_____ yes, _____ no.

If YES depth of formation *6'*

Why *Keep back surface water + mud*

Drillers Remarks: _____

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<i>1 to 25' Surface clay + Rock</i>	<i>20</i>	<i>25</i>
<i>25 to 45 Gray shale</i>		
<i>6" Rock at 144'</i>	<i>20</i>	<i>45</i>
<i>45 to 55 Gray shale + Rock</i>		
<i>(5' Rock 50 to 55)</i>	<i>10</i>	<i>55</i>
<i>55 to 65 Gray shale</i>		
<i>(+ 4 ft Rock at 60' to 64 = 1 ft Blue shale)</i>	<i>10</i>	<i>65</i>
<i>65 to 75 all Blue shale</i>	<i>10</i>	<i>75</i>
<i>75 to 85 Light Blue shale</i>		
<i>+ 2 umbos</i>	<i>10</i>	<i>85</i>
<i>85 to 95 Greeny Light Blue Gumbo</i>	<i>10</i>	<i>95</i>
<i>95 to 120 ✓</i>	<i>30</i>	<i>125</i>
<i>18" Gravel 123 to 125</i>		
<i>125 to 165 Blue shale + Gravel</i>	<i>40</i>	<i>165</i>
<i>Mixed</i>		
<i>165 to 189 Sand light Grey</i>	<i>24</i>	<i>189</i>
<i>Set Rod Pump Jensen 1/2 HP</i>		
<i>14" Eureka Cylinders at 126 feet Pump 5 Gpm per m</i>		



Well No.

1942

1943

1944

1945

1946

1947

1948

1949

1950

1951

1952

1953

1954

1955

1956