

WASH.  
D129  
Elog # 80

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

**CODED**

WATER WELL DRILLERS LOG

CI4823-3908

February 20, 1973 Singer-Layne Central Division Washington 08  
date well completed firm name county well located

LANDOWNER: City of Greenville

Greenville, Mississippi

(mailing address)

WELL LOCATION:

sec. 18 T 18 N R 8 ~~SE~~ W  
Greenville  
(distance) (direction) (nearest town)

WELL PURPOSE: municipal  
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 18 x 12
- (2) total depth (feet) 554'
- (3) static water level (feet) 75 below top of ground.
- (4) casing steel 4' blank inner casing (material) 69' (depth) 12" 18" (size) if telescope see back.
- (5) screen 70' 546' (length) (depth to top)
- 8' BPV 12" Armco (size) (material)
- (6) pump 75 1200 (HP) (yield gpm)  
electric (type power)
- (7) electric log yes (yes or no)  
USGS (organization running log)
- (8) how well bottom plugged BPV

description of formations encountered

from to

Clay	0	37
Sand	37	79
Coarse sand, pea gravel	79	89
Coarse sand, gravel	89	91
Hard clay	91	143
Clay	143	233
Sandy clay	233	265
Sandy clay & sand strks	265	314
Rock	314	315
Shale	315	331
Sandy shale & sand	331	345
Sand with strks. shale	345	443
Shale	443	457
Sand	457	554
Shale	554	561

**CONF**

172  
70  
542  
572

546  
70  
616


546  
70  
616

DRILLERS REMARKS:

FEB 22 1973  
MAR 22 1973

If well telescopes please  
sketch and show depths.

GROUND LEVEL



SECTION \_\_\_\_\_

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,  
show locations of each on sketch.