

**MISSISSIPPI DEPARTMENT OF NATURAL RESOURCES**

Bureau of Land and Water Resources

COUNTY WELL LOCATED <i>Washington</i>	
WELL NUMBER <i>D 190</i>	CODED
DATE WELL COMPLETED <i>11-23-89</i>	

PERMIT NUMBER <i>145P OR 146A</i>
NAME OF DRILLING FIRM <i>Schult. Drilling</i>

**CODED** P.O. Box 10631  
Jackson, Mississippi 39209  
**WATER-WELL DRILLERS LOG**

NAME & MAILING ADDRESS OF LANDOWNER <i>Church of Jesus Christ of Latter Day Saints Rt. 3, Greenville MS</i>		
WELL LOCATION: SEC	TOWNSHIP	RANGE
<i>14</i>	<i>18</i>	<i>8</i>
DISTANCE DIRECTION NEAREST TOWN <i>2</i> Miles <i>S</i> of <i>Greenville</i>		
OTHER LANDMARK		
WELL PURPOSE: Home, <u>Irrigation</u> , Municipal, Industrial, Fish Pond, etc.		

PUMP DATA		
PUMP TYPE (Circle One): <u>Submersible</u> Turbine, Jet, Flowing Well, Other (Describe) _____		
POWER TYPE (Circle One): <u>Electric</u> Tractor, Diesel, Gasoline, Butane, Other (Describe) _____		
Pump Capacity (GPM) <i>50</i>	No. of Stages <i>10</i>	Setting Depth <i>105</i> FT.
PUMP TEST		
Well yielded <i>55</i> GPM with a drawdown of <i>-</i> ft. after _____ hours of pumping		

WELL DATA		
Well Depth <i>330</i>	Casing Diameter (in.) <i>4 x 3</i>	Casing Length (Ft.) <i>300</i>
Type of Casing <i>Pvc</i>	Hole Depth <i>340</i>	Depth to Static Water Level <i>44</i>
TYPE OF COMPLETION: (Circle One or More): Gravel Packed, Underreamed, Telescoped, <u>Natural Development</u> , Open Hole, Other (Describe) _____		
Top of Lap Pipe or Reduction in Casing <i>120'-4"</i> FEET IF TELESCOPED OR MORE THAN <i>180'-3"</i> ONE SCREEN: USE BACK PAGE		

LOG DATA	
TYPE OF LOG RUN (Circle One): <u>No Log Run</u> , Electric, Gamma Ray, Density, Sonic, Neutron, Other (Describe) _____	
Name of Organization Running Log	

SCREEN DATA		
Diameter - Inches <i>3"</i>	Length - Feet <i>30'</i>	Slot Size - Inches <i>.010</i>
Screen Type <i>Pvc</i>	Depth to Bottom - Feet <i>330</i>	

GEOLOGIC DATA (Office Use Only)			
Surface Elev.	Geologic Unit	Unit Thickness	Depth to Top
Subs. SWL	Date	Analysis	Acquifer Test
Driller's Remarks <b>RECEIVED</b> <i>JAN 09 1990</i>			

DESCRIPTION OF FORMATIONS ENCOUNTERED	FROM	TO	FORMATIONS (Continued)	
			FROM	TO
<i>Clay</i>	<i>0</i>	<i>33</i>		
<i>Sand</i>	<i>33</i>	<i>86</i>		
<i>Clay</i>	<i>86</i>	<i>240</i>		
<i>Sand</i>	<i>240</i>	<i>340</i>		

IF MORE SPACE IS NEEDED, USE BACK

If well telescopes please sketch and show depths.

GROUND LEVEL

4"


120'

3"

180'

Screen  
\_\_\_\_\_

30'



SECTION 14

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen,  
show location of each on sketch.