

E45

MISSISSIPPI  
BOARD OF WATER COMMISSIONERS  
416 North State Street  
Jackson, Mississippi 39201

WATER WELL DRILLERS LOG

Washington

1-68

(18)

1-

19 68 DYERWELL TR. WASID.

date well completed

firm name

county well located

LANDOWNER: WESTON ABSHIRE

RR 6-VILLE

MISS.

(mailing address)

WELL LOCATION:

sec. 20 T 18 N R 7 E  
4 miles W of LELAND  
(distance) (direction) (nearest town)

WELL PURPOSE:

(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

- (1) diameter (inches) 4" x 2"
- (2) total depth (feet) 608
- (3) static water level (feet) 23 below above top of ground.
- (4) casing PVC 16 and 588' (material) (depth)
- (size) if telescope see back.
- (5) screen 20' 588' (length) (depth to top)  
2" STAINLESS STEEL (size) (material)
- (6) pump 2 35 (HP) (yield gpm)  
ELEC. JET (type power)
- (7) electric log YES (yes or no)  
U.S. GEO. E-109 '62 (organization running log)
- (8) how well bottom plugged VALVE

description of formations encountered


from

to

CLAY	0	18
SAND	18	52
GRAVEL	82	109
BLUE CLAY	108	165
CLAY SAND STREAKS	165	197
SANDY SHALE	197	248
SHALE (Gummy)	248	265
ROCK	265	266
SAND	266	362
ROCK	362	363
SAND CLAY STREAKS	363	442
CLAY & SHALE	442	476
SAND	476	522
CLAY	522	545
SANDY SHALE	545	575
SAND	575	615
CLAY	615	630

E-109

Alluvium aquifer 40 - 109



DRILLERS REMARKS:

