

WASH. MISSISSIPPI BOARD OF WATER COMMISSIONERS

26
6-5-58

WATER WELL DRILLERS LOG CODED

10/11/65
C534

Date: June 5, 1958, Driller: Layne-Central Company County Washington

(Name)

(1) Owner of Land: J. C. Willis, Jr.
(Name)

Hollandale, Mississippi
(Address)

(2) Location: 1/4, 1/4, Sec. 5-14N 9W, T. R.,

10 miles southwest of Hollandale
(distance) (direction) (Nearest Town)

(3) Topography: flat
(Hilly) (Flat) (Level)

(4) Purpose of Well: irrigation
(Domestic Irrigation, Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Clay	28	28
Fine brown sand	8	36
Coarse sand	16	52
Coarse sand & some pea rock	15	67
Fine blue sand	6	73
Sand & pea rock	9	82
Sand & gravel	20	102
Coarse sand & gravel	16	118
Bottom out in fine sand		119

Information upon completion of well:

- (1) Diameter 18x16 inches.
- (2) Total Depth 119 feet.
- (3) Water Level 8' 3" feet below top of ground.
- (4) Cased to 77', Size 18"
- (5) Screen: Size 16", Length 40'
- (6) Were any formations sealed against pollution?

CODED

Insuff. info.
to locate

yes, no no.


If YES depth of formation.

Why

Drillers Remarks:

2400 GPM.

Engine drive.



(Use Back Side)

Well No.

