

C3

6-1-62

3P

WATER WELL DRILLERS LOG


Date: June 1, 1962, Driller: Porter Drilling & Svc. County Wayne  
 (Name)

(1) Owner of Land:	Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>L. C. Jones</u> (Name)	<u>stiff red clay</u>	<u>15</u>	<u>15</u>
<u>Wivance, Miss</u> (Address)	<u>blue chalk</u>	<u>35</u>	<u>50</u>
(2) Location: <u>NE 1/4, SW 1/4, Sec 27 T10 R 7</u>	<u>rock</u>	<u>1</u>	<u>51</u>
<u>3/4</u> miles <u>SE</u> of <u>Wivance</u> (distance) (direction) (Nearest Town)	<u>blue chalk</u>	<u>112</u>	<u>163</u>
(3) Topography: <u>Hilly</u> (Hilly) (Flat) (Level)	<u>strata of rocks to</u>		
(4) Purpose of Well: <u>domestic</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>blue chalk</u>	<u>21</u>	<u>184</u>
	<u>hard rock</u>	<u>2 1/2</u>	<u>186 1/2</u>
	<u>tight sand &amp; chalk</u>	<u>6 1/2</u>	<u>193</u>
	<u>blue chalk</u>	<u>3</u>	<u>196</u>
	<u>strata of rock &amp; blue</u>		
	<u>chalk</u>	<u>14</u>	<u>210</u>
	<u>blue chalk</u>	<u>55</u>	<u>265</u>
	<u>lignite, chalk &amp; sand</u>	<u>5</u>	<u>270</u>
	<u>course sand, shale &amp;</u>		
	<u>lignite</u>	<u>6</u>	<u>276</u>
	<u>rock</u>	<u>1</u>	<u>277</u>
	<u>sand, lignite, shale, chalk</u>	<u>8</u>	<u>285</u>
	<u>chalk, lignite, &amp; sand</u>	<u>7</u>	<u>292</u>
	<u>blue chalk</u>	<u>20</u>	<u>312</u>
	<u>mostly clean medium</u>		
	<u>sand gradually becoming</u>		
	<u>more lignite &amp; chalk</u>		
	<u>toward bottom</u>	<u>16</u>	<u>328</u>
	<u>stopped on chalk</u>		<u>328</u>

Information upon completion of well:

- (1) Diameter 2' inches.
- (2) Total Depth 328 feet.
- (3) Water Level 31 feet below top of ground.
- (4) Cased to 317 1/2, Size 2'
- (5) Screen: Size 1 1/4, Length 12
- (6) Were any formations sealed against pollution?  
 yes,  no.

If YES depth of formation \_\_\_\_\_  
 Why \_\_\_\_\_  
 Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

