

D 16

10-2-64

WATER WELL DRILLERS LOG

Date: Oct 2, 1964, Driller: Porter Drilling & Sup County Wayne
 3 P (Name)

(1) Owner of Land: Robert Jones Jr.
 (Name)
Box 4 Waynesboro, Miss.
 (Address)
 (2) Location: NE 1/4, NW 1/4, Sec. 19 T10R6
12 miles north of Waynesboro
 (distance) (direction) (Nearest Town)
 (3) Topography: Hilly
 (Hilly) (Flat) (Level)
 (4) Purpose of Well: domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>red sand</u>	<u>8</u>	<u>8</u>
<u>blue chalk</u>	<u>16</u>	<u>24</u>
<u>grey chalk</u>	<u>11</u>	<u>35</u>
<u>blue chalk</u>	<u>103</u>	<u>138</u>
<u>rock strata</u>	<u>50</u>	<u>188</u>
<u>blue chalk</u>	<u>50</u>	<u>238</u>
<u>chalk, lignite & sand</u>	<u>7</u>	<u>245</u>
<u>sea shell</u>	<u>4</u>	<u>249</u>
<u>chalk, sand & lignite</u>	<u>9</u>	<u>258</u>
<u>fine dirty sand & shell</u>	<u>15</u>	<u>273</u>
<u>chalk</u>	<u>14</u>	<u>287</u>
<u>sand & lignite</u>	<u>31</u>	<u>318</u>
<u>stopped on chalk</u>		

Information upon completion of well:

(1) Diameter 2" inches.
 (2) Total Depth 318' feet.
 (3) Water Level 93' feet below top of ground.
 (4) Cased to 273', Size 2"
 (5) Screen: Size 1/4", Length 18'
 (6) Were any formations sealed against pollution?
 _____ yes, X no.

If YES depth of formation _____
 Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

