

Wayne
F 38

WATER WELL DRILLERS LOG

C. P. CLARK

11-12-60

WATER WELL DRILLING

ROUTE TWO

Date: 11/12, 1960, Driller:

COPIED
12/69 JMB
Wayne

LAUREL, MISS.

(1) Owner of Land: Plant Home Church
(Name)
Rt #6 Laurel, Miss
(Address)
32 9th St W
(2) Location: 1/4, 1/4, Sec. T R
15 miles East of Laurel
(distance) (direction) (Nearest Town)
(3) Topography: Flat
(Hilly) (Flat) (Level)
(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Material Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
0-15 Clay	15	
15-25 Sand	10	
25-100 Clay	75	
100-140 Mixed Clay Sand	40	
140-180 Sand	40	
180-240 Mixed Clay	60	
240-247 Red Sand	7	
247-265 Hard Clay	18	
265-267 fine Rocks	2	
267-268 Clay	1	
268-271 fine Rocks	3	
271-275 Hard Clay	4	
275-277 1/2 Rough Rocks	2 1/2	
277 1/2 - 280 Clay	2 1/2	
280-290 Clay Shells	10	
290-340 Green Clay	50	
340-348 Rocks	8	
348-353 Clay	5	
353-357 Rocks	4	
357-400 Clay	43	


Information upon completion of well:

(1) Diameter 2 inches.
(2) Total Depth 400 feet.
(3) Water Level 103 feet below top of ground.
(4) Cased to 270, Size 2
(5) Screen: Size None, Length _____
(6) Were any formations sealed against pollution?
✓ yes, _____ no.

If YES depth of formation 270

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

