

WAYNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

G 41

2-3-66

WATER WELL DRILLERS LOG

Date: Feb 3, 1966, Driller: Porter Drilling (Name) Wayne County  
3P

(1) Owner of Land: George W. Hatley  
 (Name)  
Box 1 Shubuta, Miss  
 (Address)

(2) Location: SW 1/4, NE 1/4, Sec. 5 T9R8  
15 miles NW of Waynesboro  
 (distance) (direction) (Nearest Town)

(3) Topography: Hilly  
 (Hilly) (Flat) (Level)

(4) Purpose of Well: domestic  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>top soil</u>	<u>6</u>	<u>6</u>
<u>red clay</u>	<u>9</u>	<u>15</u>
<u>blue chalk</u>	<u>10</u>	<u>25</u>
<u>fine blue sand</u>	<u>13</u>	<u>38</u>
<u>blue chalk</u>	<u>21</u>	<u>69</u>
<u>rock strata</u>	<u>10</u>	<u>79</u>
<u>blue chalk</u>	<u>19</u>	<u>98</u>
<u>clean medium sand</u>	<u>3</u>	<u>101</u>
<u>sand &amp; chalk streak</u>	<u>2</u>	<u>103</u>
<u>green chalk</u>	<u>15</u>	<u>118</u>
<u>harder rock</u>	<u>26</u>	<u>144</u>
<u>white chalk</u>	<u>7</u>	<u>151</u>

Information upon completion of well:

(1) Diameter 2" inches.

(2) Total Depth 151' feet.


(3) Water Level 69' feet below top of ground.

(4) Cased to 119', Size 2"

(5) Screen: Size none, Length \_\_\_\_\_

(6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes, X no.

If YES depth of formation \_\_\_\_\_  
 Why \_\_\_\_\_  
 Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

