

WAYNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

M29

10-4-62

WATER WELL DRILLERS LOG

Date: Oct 4, 1962, Driller: Porter Drilling & Sup. County: Wayne
 130 (Name)

(1) Owner of Land: C. C. Davis Jr.
 (Name)
Waynesboro Miss
 (Address)

(2) Location: NE 1/4, NW 1/4, Sec. 5 T8R8.
10 miles west, of Waynesboro
 (distance) (direction) (Nearest Town)

(3) Topography: hilly
 (Hilly) (Flat) (Level)

(4) Purpose of Well: domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
red sandy clay	10	10
red sand	5	15
chalk	19	34
rock	1	35
sandy chalk	17	52
fine sand	14	66
med. sand	3	69
med. coarse sand	5	74

Information upon completion of well:

(1) Diameter 2" inches.

(2) Total Depth 74' feet.

(3) Water Level 43' feet below top of ground.

(4) Cased to 70', Size 2".


(5) Screen: Size 1/4", Length 6'.

(6) Were any formations sealed against pollution?
 _____ yes, X no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

MEMORANDUM FOR THE RECORD

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50

10/10/50