

WAYNE  
N8  
5-13-64

WATER WELL DRILLERS LOG

Date: May 13, 1964, Driller: Porter Drilling & Log County: Wayne  
(Name)


(1) Owner of Land: Woodrow Jones  
(Name)  
At 3 Waynesboro, Miss.  
(Address)  
(2) Location: SE 1/4, SW 1/4, Sec. 35 T8 R7  
5 miles south of Waynesboro  
(distance) (direction) (Nearest Town)  
(3) Topography: hilly  
(Hilly) (Flat) (Level)  
(4) Purpose of Well: domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>red clay</u>	<u>8</u>	<u>8</u>
<u>chalk</u>	<u>24</u>	<u>32</u>
<u>sand</u>	<u>18</u>	<u>50</u>
<u>chalk</u>	<u>23</u>	<u>73</u>
<u>sand</u>	<u>3</u>	<u>76</u>
<u>chalk</u>	<u>11</u>	<u>87</u>
<u>rock</u>	<u>1</u>	<u>88</u>
<u>hard sand</u>	<u>3</u>	<u>91</u>
<u>chalk</u>	<u>9</u>	<u>100</u>
<u>hard sand &amp; chalk</u>	<u>21</u>	<u>121</u>
<u>sand</u>	<u>12</u>	<u>133</u>

Information upon completion of well:

(1) Diameter 2" inches.  
(2) Total Depth 133' feet.  
(3) Water Level 71' feet below top of ground.  
(4) Cased to 122', Size 2"  
(5) Screen: Size 1/4", Length 8'  
5' .006"  
3' .008"  
(6) Were any formations sealed against pollution?  
\_\_\_\_\_ yes, X no.

If YES depth of formation \_\_\_\_\_  
Why \_\_\_\_\_  
Drillers Remarks: \_\_\_\_\_



Well No. \_\_\_\_\_

Retain this copy for your office files.

