

WAYNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

N 28

11-6-62

WATER WELL DRILLERS LOG

Date: Nov 6, 1962 Driller: Porter Drilling Co County Wayne  
 (Name)


(1) Owner of Land: Clyde Armstrong  
 (Name)  
Box 1 Waynesboro, Miss  
 (Address)  
 (2) Location: NW 1/4, NE 1/4, Sec. 2 T8R8,  
8 miles west of Waynesboro  
 (distance) (direction) (Nearest Town)  
 (3) Topography: Hilly  
 (Hilly) (Flat) (Level)  
 (4) Purpose of Well: domestic  
 (Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
red clay	25	25
coarse sand	25	50
chalk & sand	34	84
sand rock	1	85
course red sand & gravel	7	92
course slightly red sand	10	102
course red sand & peagavel	10	112
course white sand	10	122
course white sand & peagavel	13	135
stayed white steel in sand & gravel		

Information upon completion of well:

(1) Diameter 2" inches.  
 (2) Total Depth 135 feet.  
 (3) Water Level 66' feet below top of ground.  
 (4) Cased to 126', Size 2"  
 (5) Screen: Size 1 1/4", Length 5'  
Johnson standard steel  
 (6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes, X no.

If YES depth of formation \_\_\_\_\_  
 Why \_\_\_\_\_  
 Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

THE HISTORY OF THE

REIGN OF

CHARLES THE FIRST

BY

JOHN BURNET

OF

SCOTLAND

AND

OF

ENGLAND

IN

SEVEN VOLUMES

THE SECOND

VOLUME

LONDON

1704