

Wayne
 N44
 B-66

MISSISSIPPI BOARD OF WATER COMMISSIONERS

WATER WELL DRILLERS LOG

Date: Aug 30, 19 66, Driller: Porter Drilling & Pump County Wayne
 (Name)


(1) Owner of Land: H. D. Cooley
 (Name)
At 3 Waynesboro, Miss
 (Address)
 (2) Location: SE 1/4, SE 1/4, Sec. 8 T. 8 R. 7
4 miles west of Waynesboro
 (distance) (direction) (Nearest Town)
 (3) Topography: Hilly
 (Hilly) (Flat) (Level)
 (4) Purpose of Well: domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)

| Description & Color of Materials Sand, Clay, Red Clay, Shell, etc. | Thick- ness Feet | Depth Feet |
|---|------------------------|---------------|
| red clay | 5 | 5 |
| red chalk | 20 | 25 |
| blue chalk | 20 | 45 |
| fine sand | 20 | 65 |
| med sand | 25 | 90 |
| course sand | 18 | 108 |
| blue chalk | 4 | 112 |
| sand | 8 | 120 |
| blue chalk | 12 | 132 |
| course sand | 6 | 138 |
| course sand & chalk | 10 | 148 |
| blue chalk | 3 | 151 |
| rock strata | 45 | 196 |
| sand ? | 3 | 197 |
| blue chalk | 9 | 205 |
| med course sand | 35 | 240 |
| blue chalk | 31 | 271 |
| Vicksburg honeycomb rocks | 25 | 296 |

Information upon completion of well:

(1) Diameter 2" inches.
 (2) Total Depth 296' feet.
 (3) Water Level 97' feet below top of ground.
 (4) Cased to 273', Size 2"
 (5) Screen: Size none, Length _____
 (6) Were any formations sealed against pollution?
 _____ yes, X no.

If YES depth of formation _____
 Why _____
 Drillers Remarks: _____



(Use Back Side)

Well No.

