

WAYNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

S6

10-18-63

WATER WELL DRILLERS LOG

Date: Oct 18, 1963, Driller: Porter Drilling & Log County Wayne
 (Name)

(1) Owner of Land: Cecaron Pittman
 (Name)
Rt 3 Waynesboro
 (Address)
 (2) Location: SE 1/4 SE 1/4, Sec. 22 T7 R 7
3 miles S of Clava
 (distance) (direction) (Nearest Town)
 (3) Topography: level
 (Hilly) (Flat) (Level)
 (4) Purpose of Well: domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)


Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>yellow clay</u>	<u>8</u>	<u>8</u>
<u>chalk</u>	<u>4</u>	<u>12</u>
<u>red sand & chalk</u>	<u>14</u>	<u>26</u>
<u>soft chalk</u>	<u>4</u>	<u>30</u>
<u>blue chalk</u>	<u>47</u>	<u>77</u>
<u>streaks of sand & chalk</u>	<u>13</u>	<u>90</u>
<u>clean tight sand</u>	<u>8</u>	<u>98</u>
<u>streaks sand & chalk</u>	<u>22</u>	<u>120</u>
<u>stiff chalk</u>	<u>19</u>	<u>139</u>
<u>clean med. sand</u>	<u>14</u>	<u>153</u>

Information upon completion of well:

(1) Diameter 2" inches.
 (2) Total Depth 153' feet.
 (3) Water Level 41 feet below top of ground.
 (4) Cased to 148, Size 2'
 (5) Screen: Size 1 1/4, Length 5'
Johnson S. S
 (6) Were any formations sealed against pollution?
 _____ yes, X no.

If YES depth of formation _____
 Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

[The page contains extremely faint and illegible text, likely bleed-through from the reverse side of the document. The text is too light to transcribe accurately.]