

S 40

10-6-65

WATER WELL DRILLERS LOG


Date: Oct 6, 1965, Driller: Porter Drilling & Inc County: Wayne
 (Name)

(1) Owner of Land:	Description & Color of Materials	Thick-ness Feet	Depth Feet
<u>Big Creek Baptist Church</u> (Name)	<u>red clay</u>	<u>10</u>	<u>10</u>
<u>Rt 3 Waynesboro, Miss</u> (Address)	<u>sand & chalk</u>	<u>8</u>	<u>18</u>
(2) Location: <u>NW 1/4, NW 1/4, Sec. 11 T. 7 R. 7</u>	<u>chalk blue</u>	<u>70</u>	<u>88</u>
<u>6</u> miles <u>S.</u> of <u>Waynesboro</u> (distance) (direction) (Nearest Town)	<u>red chalk</u>	<u>8</u>	<u>94</u>
(3) Topography: <u>hilly</u> (Hilly) (Flat) (Level)	<u>red sand</u>	<u>2</u>	<u>96</u>
(4) Purpose of Well: <u>domestic</u> (Domestic Irrigation Municipal, Industrial, Other)	<u>red chalk & sand</u>	<u>11</u>	<u>107</u>
	<u>thin rock</u>		<u>107</u>
	<u>red chalk & sand streak</u>	<u>13</u>	<u>120</u>
	<u>chalk</u>	<u>20</u>	<u>140</u>
	<u>red sand</u>	<u>9</u>	<u>149</u>
	<u>red chalk</u>	<u>2</u>	<u>151</u>
	<u>Coarse red sand</u>	<u>5</u>	<u>156</u>
	<u>Chalk</u>	<u>20</u>	<u>176</u>
	<u>fine sand & chalk</u>	<u>6</u>	<u>182</u>
	<u>fine sand mostly chalk</u>	<u>21</u>	<u>203</u>
	<u>thin rock</u>		<u>203</u>
	<u>fine sand</u>	<u>3</u>	<u>206</u>
	<u>coarse sand</u>	<u>7</u>	<u>213</u>
	<u>stayed on chalk</u>		

Information upon completion of well:

- (1) Diameter 2" inches.
- (2) Total Depth 213' feet.
- (3) Water Level 105' feet below top of ground.
- (4) Cased to 210', Size 2"
- (5) Screen: Size 1 1/4", Length 3'
Johnson SS. 8 slot
- (6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation _____
 Why _____
 Drillers Remarks: _____



(Use Back Side)

Well No. _____

