

Wayne

MISSISSIPPI BOARD OF WATER COMMISSIONERS

541

11-66

WATER WELL DRILLERS LOG

Date: Nov 2, 1966, Driller: Porter Drilling & Log. County: Wayne

(Name)

(1) Owner of Land:	Description & Color of Materials	Thickness Feet	Depth Feet
<u>Mrs Ostra Velhain</u> (Name)	Sand, Clay, Red Clay, Shell, etc.		
<u>At 3 Waynesboro, Miss</u> (Address)	<u>red clay</u>	10	10
(2) Location: <u>NW 1/4, NE 1/4, Sec. 11 T7R7</u>	<u>soupy sand</u>	6	16
<u>3</u> miles <u>NE</u> of <u>Clara</u> (distance) (direction) (Nearest Town)	<u>red chalk</u>	10	26
(3) Topography: <u>hilly</u> (Hilly) (Flat) (Level)	<u>blue chalk</u>	59	85
(4) Purpose of Well: <u>domestic</u> (Domestic Irrigation, Municipal, Industrial, Other)	<u>thin rock</u>		85
	<u>tight red sand</u>	4	89
	<u>chalk & sand</u>	16	105
	<u>blue chalk</u>	5	110
	<u>red chalk & sand</u>	34	144
	<u>med coarse gtl sand</u>	5	149
	<u>mostly chalk</u>	31	180
	<u>mostly sand</u>	18	198
	<u>clean coarse sand</u>	9	207
	<u>course sand & chalk</u>	13	220
	<u>mostly chalk</u>	10	230
	<u>sand & chalk</u>	26	256
	<u>stiff chalk</u>	41	297
	<u>rock stratus</u>	18	315
	<u>blue chalk</u>	11	326
	<u>rock stratus</u>	17	343
	<u>blue chalk</u>	98	441
	<u>Vicksburg honeycom</u>	30	471


Information upon completion of well:

- (1) Diameter 2" inches.
- (2) Total Depth 471' feet.
- (3) Water Level 95' feet below top of ground.
- (4) Cased to 441, Size 2"
- (5) Screen: Size none, Length _____
- (6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation _____

Why _____

Drillers Remarks: _____



(Use Back Side)

Well No.

