

WAYNE
U 66
3-8-73

MISSISSIPPI
BOARD OF WATER COMMISSIONERS
416 North State Street
Jackson, Mississippi 39201

CODED

WATER WELL DRILLERS LOG

3/8 1973 CARRS well service WAYNE
date well completed firm name county well located

LANDOWNER: RAY NAPIER
RT 1 BUCKATUNNA MISS
(mailing address)

WELL LOCATION:
sec. 28 T 2 N R. 5 E W
S W
(distance) miles (direction) of (nearest town)

WELL PURPOSE: HOME
(home, irrigation, municipal, industrial)

WELL COMPLETION DATA:

(1) diameter (inches) 4 1/2"
(2) total depth (feet) 114
(3) static water level (feet) 55 ^{below} above top of ground.
(4) casing PVC 110 (material) (depth) (size) If telescope see back.
(5) screen 4" (length) 110' (depth to top) 2" (size) PVC (8564) (material)
(6) pump 1 (HP) 6 (yield gpm)
Elec 4 (type power)
(7) electric log No (yes or no)
(organization running log)
(8) how well bottom plugged 2" B.W.V.

description of formations encountered	from	to
Top Soil	0	1
Yellow Sand	1	12
White Sand w/ Clay Balls	12	16
Coarse white sand w/ w. clay	16	25
Red gravel w/ clay	25	31
Blue + pink clay	31	40
yellow clay	40	43
Blue Clay	43	68
Med Brownish Tight Sand	68	73
Pinkish + Blue Clay	73	85
Pink limey clay	85	88
Fine white sand	88	97
Pink Clay	97	100
Med white sand	100	114
still in sand when lost Ret @ 114'		

CODED


DRILLERS REMARKS: Lost Ret @ 114' Pumped CS9 + screen in w/ 1" pipe through B.W.V.

MISSISSIPPI BOARD OF WATER COMMISSIONERS

MISS. Bd. OF WATER COMMISSIONERS

If well telescopes please sketch and show depths.

GROUND LEVEL



SECTION _____

Please indicate well location X.

ADDITIONAL INFORMATION

If more than one screen, show locations of each on sketch.