

WAYNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

X2

10-16-63

WATER WELL DRILLERS LOG

Date: Oct 16, 1963, Driller: Pate Drilling & Log Co. Wayne  
(Name)

- (1) Owner of Land: Jack Mills  
(Name)  
Rt 3 Waynesboro, Miss  
(Address)
- (2) Location: NE 1/4, NW 1/4, Sec. 3 T.6 R.7,  
5 miles S of Clara  
(distance) (direction) (Nearest Town)
- (3) Topography: Hilly  
(Hilly) (Flat) (Level)
- (4) Purpose of Well: domestic  
(Domestic Irrigation  
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
red clay	12	12
yellow chalk	16	28
thin rock		28
blue chalk	18	46
streaks of sand & chalk	14	60
blue chalk	36	96
streaks sand & chalk	12	108
grey chalk	31	139
sand & chalk	7	146
stiff blue chalk	14	160
med. clean sand	8	168
chalk & streak of sand	24	192
clean med. sand	14	206
stop on chalk		


Information upon completion of well:

- (1) Diameter 2" inches.
- (2) Total Depth 206' feet.
- (3) Water Level 63' feet below top of ground.
- (4) Cased to 194', Size 2"
- (5) Screen: Size 1 1/4", Length 12'
- (6) Were any formations sealed against pollution?  
 \_\_\_\_\_ yes, X no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: \_\_\_\_\_



(Use Back Side)

Well No.

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...

...the ...