

WAYNE MISSISSIPPI BOARD OF WATER COMMISSIONERS

X3

5-4-65

WATER WELL DRILLERS LOG

Date: May 4, 1965, Driller: Porter Drilling & Log Co County: Wayne  
 Elev. 190± (Name) Haines 89, 10

| (1) Owner of Land:  | Description & Color of Materials<br>Sand, Clay, Red Clay, Shell, etc. | Thick-ness Feet | Depth Feet |
|---|---|-----------------|------------|
| <u>J. L. Martin Jr. Farmer</u><br>(Name)  | <u>red clay</u>   | <u>8</u>        | <u>8</u>   |
| <u>Waynesboro Miss</u><br>(Address)   | <u>red chalk</u>  | <u>2.5</u>      | <u>33</u>  |
| (2) Location: <u>SE 1/4, NE 1/4, Sec. 3 T6 R7</u>   | <u>blue chalk</u>   | <u>5</u>        | <u>38</u>  |
| <u>14</u> miles <u>south</u> of <u>Waynesboro</u><br>(distance) (direction) (Nearest Town)          | <u>red sand &amp; chalk</u>   | <u>7</u>        | <u>45</u>  |
| (3) Topography: <u>hilly</u><br>(Hilly) (Flat) (Level)  | <u>blue chalk</u>   | <u>39</u>       | <u>83</u>  |
| (4) Purpose of Well: <u>chicken houses</u><br>(Domestic Irrigation<br>Municipal, Industrial, Other) | <u>med coarse white sand</u>  | <u>7</u>        | <u>90</u>  |
|   | <u>chalk</u>  | <u>2</u>        | <u>92</u>  |
|   | <u>med white sand</u>   | <u>11</u>       | <u>103</u> |
|   | <u>coarse white sand</u>  | <u>7</u>        | <u>110</u> |
|   | <u>blue chalk</u>   | <u>10</u>       | <u>120</u> |
|   | <u>blue chalk with</u>  | <u>83</u>       | <u>203</u> |
|   | <u>streaks of fine sand</u>   |                 |            |
|   | <u>blue chalk</u>   | <u>33</u>       | <u>236</u> |
|   | <u>fine sand &amp; chalk</u>  | <u>15</u>       | <u>251</u> |
|   | <u>med coarse sand</u>  | <u>9</u>        | <u>260</u> |
|   | <u>stopest white steel</u>  |                 |            |
|   | <u>in sand</u>  |                 |            |


Information upon completion of well:

- (1) Diameter 2" inches.
- (2) Total Depth 260' feet.
- (3) Water Level 64' feet below top of ground.
- (4) Cased to 241', Size 2"
- (5) Screen: Size 1 1/4", Length 8'  
Johanson S.S. #7 & #8 bit
- (6) Were any formations sealed against pollution?  
 yes,  no.

If YES depth of formation \_\_\_\_\_

Why \_\_\_\_\_

Drillers Remarks: 1 1/2 HP Jet 8 gpm



Well No. \_\_\_\_\_

