

Y15

WATER WELL DRILLERS LOG

Wayne  
Clarks

Date: 9-4, 1961, Driller: Peoples & Rutledge County, Clarks  
(Name)

(1) Owner of Land: Drew White  
(Name)  
Rt 1, State Line, Miss  
(Address)

(2) Location:  $\frac{1}{4}$ ,  $\frac{1}{4}$ , Sec. 32 T16R64  
Wayne County  
miles, of  
(distance) (direction) (Nearest Town)

(3) Topography: Hilly  
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic  
(Domestic Irrigation  
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
<u>yellow sandy clay</u>	<u>52</u>	<u>52</u>
<u>Blue clay</u>	<u>28</u>	<u>80</u>
<u>White Sand</u>	<u>6</u>	<u>86</u>
<u>Blue Shale</u>	<u>19</u>	<u>105</u>
<u>Limestone</u>	<u>5</u>	<u>110</u>
<u>Blue sandy shale</u>	<u>30</u>	<u>140</u>
<u>Gray clay</u>	<u>13</u>	<u>153</u>
<u>White clay - fine</u>		
<u>sand lentils</u>	<u>30</u>	<u>183</u>
<u>White Sand</u>	<u>72</u>	<u>255</u>

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 255 feet.

(3) Water Level 110 feet below top of ground.


(4) Cased to 249, Size 2"

(5) Screen: Size 2", Length 6'

(6) Were any formations sealed against pollution?  
\_\_\_\_\_ yes, \_\_\_\_\_ no.

If YES depth of formation \_\_\_\_\_  
Why \_\_\_\_\_

Drillers Remarks: Sand unusually fine at top, gradually growing coarser



(Use Back Side)

Well No.

.....

.....  
.....  
.....  
.....  
.....

.....  
.....  
.....  
.....  
.....

.....  
.....  
.....  
.....  
.....

.....  
.....  
.....  
.....  
.....

.....  
.....  
.....  
.....  
.....

.....  
.....  
.....  
.....  
.....

.....  
.....  
.....  
.....  
.....