


L 12
12-23-60



WATER WELL DRILLERS LOG

2 CODED 301

Date: 12 23 1960 Driller: Smith & Presley County Webster
(Name)

(1) Owner of Land: Buster Richardson
(Name)

(Address)

(2) Location: N 2 1/4, S 1/4, Sec 29 T12R2
7 miles N W of Stewart
(distance) (direction) (Nearest Town)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
yellow clay	8	8
black sand mixed with clay	8	16
black clay	34	50
redish Beck sand mixture	1	51
with green chalk	10	70
silt and lignite	14	84
white silt	23	106
greenish silt	27	133
grayish chalk CODED		
with a brown mixture some like lignite	14	147
blue clay with green chalk little sand	21	168
sand blue clay silt	9	176
sand blue clay silt with fine black mixture	8	184
green silt	10	194
sand silt black mix.	16	210
brown flaky clay and silt	21	231
white silt brown and black specks	9	240
hard Beck gray	6	246
light gray silt Beck plates	1 1/2	252
silt and brown flakes	21	273
silt brown flakes and black fine mixture	21	294
silt black mixture	14	308
Beck gray	3"	Well No.

Information upon completion of well:

(1) Diameter 2 inches.
(2) Total Depth 478 feet.
(3) Water Level 50 feet below top of ground.
(4) Cased to 24, Size 2"
(5) Screen: Size 10, Length _____
(6) Were any formations sealed against pollution?
_____ yes, X no.
If YES depth of formation _____
Why _____
Drillers Remarks: no sand open
hole good water

(Use Back Side)

Silt black mixture	7	315
S " " "	21	336
Silt 25% sand	21	357
Silt 75 black mixture	33	390
Gray Rock	5	395
Silt		
Silt black mixture	16	411
Silt	46	457
Silt " "	21	478