

WINSTON

K 17

CODED

WATER WELL DRILLERS LOG

K 301

11-2-60

Date: 11/21, 1960, Driller: Lo K Merritt County: Winston

(Name)

(1) Owner of Land: H. B. Woodruff
 (Name)
Louisville Mass.
 (Address) 281412

(2) Location: 1/4, 1/4, Sec. 28 T. R.
6 miles A of Louisville
 (distance) (direction) (Nearest Town)

(3) Topography: (Hilly) (Flat) (Level)

(4) Purpose of Well: Domestic
 (Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Dark brown loam sand	6	10
Mud. soft sand & clay	10	22
Soft clay, fine sand	22	36
Hard lignite	36	38
Hard blue clay	38	50
Soft blue clay	50	61
Hard lignite	61	64
Mud. soft blue clay	64	124
Hard lignite	124	132
Hard dark clay	132	162
Soft clay, lignite	162	174
Hard sand	174	224
Mud. soft blue clay		
Soft blue clay, lignite	224	240
Hard sand		
Hard sand	240	265
4" Hard rock, lignite		
Hard sand	265	279
Dark hard clay	279	290
2" rock at 290'		
Soft clay, lignite	290	307
Hard sand		
Hard light redish clay	307	323
Clay		
Dark sand	323	336
Mud. brown sand	336	344
Coarse sand	344	353
6' Brown sand		
10' Blue sand		

Information upon completion of well:

(1) Diameter 2 inches.

(2) Total Depth 353 feet.

(3) Water Level 98 feet below top of ground.

(4) Cased to 345, Size 2


(5) Screen: Size 1/4, Length 6'

(6) Were any formations sealed against pollution?
yes, no.

If YES depth of formation

Why

Drillers Remarks:



(Use Back Side)

Well No.

