

YA200

G16

6-61

WATER WELL DRILLERS LOG

CODED

Date: June, 1961, Driller: DAVID BERRY County YA200

3262 6866

(Name)

(1) Owner of Land: W. O. EVERETT
 (Name)
YA200 CITY - MISS.
 (Address)

(2) Location: 1/4, 1/4, Sec. 23 T12R2W
2 miles NE of YA200
 (distance) (direction) (Nearest Town)

(3) Topography: HILLY
 (Hilly) (Flat) (Level)

(4) Purpose of Well: DOMESTIC
 (Domestic Irrigation
 Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Kelly		20
Yellow Clay	20	40
" "	20	60
" "	20	80
" "	20	100
Blue "	20	120
" "	20	140
" "	20	160
" "	20	180
" "	20	190
Woody Branch	20	210
Rock	8"	210.8
Woody Branch	29.2	240
Sand & Shale	20	260
Sandy Shale	20	280
Sandy & Brown Shale	20	300
Hard Brown Shale	20	320
Hard Brown Shale	15	335
Sand	5	340
Sand	20	360
Sandy Brown Shale	20	380
Brown Shale	20	400
Hard Shale & Lignite	20	420
Sand & Shale	20	440
Sand	20	460
Sand & Lignite	20	480
Sand	20	500
Coarse Sand	20	520
" "	20	540
" "	20	560
" "	20	580
Sand	21	601

Information upon completion of well:

(1) Diameter 4 inches.

(2) Total Depth 601 feet.

(3) Water Level 160 feet below top of ground.


(4) Cased to 525', Size 4"

(5) Screen: Size _____, Length 30'

(6) Were any formations sealed against pollution?
 _____ yes, _____ no.

If YES depth of formation _____
Why _____

Drillers Remarks: _____



Well No.

(Use Back Side)

1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025