

MISSISSIPPI DEPARTMENT OF ENVIRONMENTAL QUALITY
Office of Land and Water Resources
P. O. Box 2309
Jackson, MS 39225
Water Well Plugging/Decommissioning Form
OLWR-DF-1 (04/08)
(601)961-5555 (601)961-5228 (fax)

FEB 13 2019
BY OLWR

Well # 1

COUNTY WELL LOCATED: Yazoo		WELL NUMBER: 16360074	
PERMIT NUMBER:		DATE WELL PLUGGED: 1-15-2019	
NAME OF FIRM PLUGGING WELL: West Water Well		TELEPHONE NUMBER: 601-428-1385	
NAME AND ADDRESS OF CURRENT LANDOWNER: Denbury Resources 5320 Legacy Dr. Plano TX 75024			
WELL LOCATION: SECTION: 1 TOWNSHIP: 10 N RANGE: 3 W			
WELL LOCATION: LATITUDE: 32.946087 LONGITUDE: -90.463067 METHOD (Check ONE): <input checked="" type="checkbox"/> USGS QUAD <input type="checkbox"/> CONVENTIONAL SURVEY <input type="checkbox"/> GPS - HAND HELD OR SURVEY GRADE			
DISTANCE: 7 mi DIRECTION: S NEAREST TOWN: Yazoo City OTHER LANDMARK:			
WELL PURPOSE (HOME, IRRIGATION, MUNICIPAL, ETC.): Big Supply			
NAME OF WELL CONTRACTOR WHO DRILLED THE WELL: West Water Well			
NAME OF LANDOWNER WHEN WELL WAS DRILLED: Denbury Resources			

WELL DATA			
WELL DEPTH: 410'		HOLE DEPTH: 410'	
CASING DIAMETER (IN.): 4	CASING LENGTH (FT.): 350	TYPE OF CASING: PVC	
DEPTH TO STATIC WATER LEVEL: 108'		DATE WELL COMPLETED: 11-8-2018	
WHY IS THE WELL BEING ABANDONED? No longer needed			

DESCRIBE HOW THE WELL OR HOLE WAS PLUGGED (AMOUNT OF CASING AND/OR SCREEN THAT WAS REMOVED OR LEFT IN HOLE, MATERIAL AND AMOUNT USED IN PLUGGING, METHOD OF PLACING MATERIAL, ETC.)


Screens were perforated w/ air operated perforator. 350'-410'

Bentonite Chips were poured through a tremie pipe, tamping intermittently. When chips were in sight, last joint of tremie was removed

Casing was cut off 5ft below surface

Concrete was used to finish filling hole & 1ft-18in. above casing cut off

I CERTIFY THAT THE WELL WAS PLUGGED OR ABANDONED IN ACCORDANCE WITH THE STATE OF MISSISSIPPI REGULATIONS.

David West

SIGNATURE

0672
MS LICENSE NUMBER
2-12-2019
DATE