

YA200

MISSISSIPPI BOARD OF WATER COMMISSIONERS

R ~~2000~~
6-28-63

WATER WELL DRILLERS LOG

Date: June 28, 19 63, Driller: J. H. Barnes County Yazoo
(Name)

(1) Owner of Land: Fred Levell
(Name)
Yazoo City, Miss (Hond Ave)
(Address)

(2) Location: NW 1/4, NE 1/4, Sec. 33 ^{10N 3W} T R
4 miles N-W of Benton
(distance) (direction) (Nearest Town)

(3) Topography: Hilly
(Hilly) (Flat) (Level)

(4) Purpose of Well: Farm
(Domestic Irrigation
Municipal, Industrial, Other)

Description & Color of Materials Sand, Clay, Red Clay, Shell, etc.	Thick- ness Feet	Depth Feet
Red Clay	30	30
Red Sand	10	40
Blue Shell	300	340
Madie Branch Sand & Shells	40	380
Shell	70	450
Sand & Shell Mixed	40	490
Water Sand	150	640
Dark Colored Shell	150	790
Shell	210	1000
Sand	15	1015
Shell	90	1105
Sand	35	1140
Scared Thin Layers of rock	20	1160
Shell	80	1240
Sand (Sporter)	46	1286

Information upon completion of well:

(1) Diameter 4" 2" inches.

(2) Total Depth 1286 feet.

(3) Water Level 180 feet below top of ground.


(4) Cased to 1242, Size 4" 42"

(5) Screen: Size 2"-006, Length 40 ft.

(6) Were any formations sealed against pollution?
 yes, no.

If YES depth of formation 336 ft. 4"
Why Cased off top soil

Drillers. Remarks:



1286

Well No.

(Use Back Side)

